

Acer K10

ACER K10



The Acer K10 Game-Portabel LED BrilliantColor DLP projector has 100 Ansi-Lumen, a contrast of 2000:1 and a WVGA 858 x 600 resolution. The service life of the LEDs is 20000 hours, which is over 13.7 years with a daily viewing time of 4 hours. Due to the brightness of 100 Ansi lumens, a picture width of 102 cm is possible. In room light, the picture should be max. 68 cm wide. With only 28 decibels of operating noise, the model is very quiet compared to others. The model was built by Acer in 2008 and is no longer current, but is still one of the very popular projectors.

Brief Introduction

Beta 2.5

Display Type

1 x 0,45" DLP Chip
WVGA 16/9 Ti Digital Light Processing Chip

Ansi-Lumen

100

44 Lux (200 cm Screen width)

Contrast

2000:1 full on/off

2000:1 full on/off

Black Level

0,0500 min. Lumen

0,022 min. Lumen

Offset

Resolution

WVGA 858 x 600

514.800 Pixel

SXGA 1280 x 1024 compressed

Video Modes

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application

Game-Portabel | Very portable, small-screen projections.

Very narrow picture width and rooms with very little light.

Light Source

LED

Light Life

20000 h.

Operating Costs

0,00 € LED

Focus

Manual

Zoom

No Zoom

Objective

F=2,0 f=17,67mm

Throw Ratio

1,97:1

Audio

Nein

Connections

D-sub 15 pin in

Cinch Video in



Ceiling Mounting

Yes, is possible.

Power


90W / 1W standby

Size WxHxD

127 x 48,5 x 122 mm (5"x1,9"x4,8") 0,74 L/dm³

Operating Noise

28dB



Key: 387 cm

Weight	0,550 kg / 1,21 lbs.	
Keystone	Vert.: +/-40° automatisch	
Illumination	85%	
Frequenz	H-sync: 31-69 kHz V-sync: 50-85 Hz	Key: 275 cm
Foot-Lamberts	4 fL / max. 102 cm screen width 14 cd/m²	
Features	■ Blackboard Modus ■ Automatic and manual vertical keystone correction ■ Kensington Slot ■ Gamma correction ■ BrilliantColor™ ■	
Screen Mirroring	Optional only Chromecast / Fire TV / Apple TV / Mi Box Ads	

Optional accessories

	Fernbedienung mit Laserpointer	MC.JMV11.00G	28,86 €
	Deckenhalterung 100-120	Halterung100	47,86 €

Status2008 Discontinued (EOL) // Last update of the data: 2026-06-08



More Details



HCinema

<https://www.projector-database.com/pro/acerk10-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.