

ACTO DX128



Brief Introduction Beta 2.5	A brief introduction to the ACTO DX128. The standard portable DLP projector has an XGA 1024 x 768 resolution and a contrast of 2600:1. The projector will be able to illuminate a picture width of 493 cm well. However, if room light is available, the image width should ideally not exceed 329 cm. The model was built by ACTO in 2011 and is no longer current.
Display Type	1 x 0,55" DDP2431 DLP Chip XGA 4/3 Ti Digital Light Processing Chip
Ansi-Lumen	Projector: 3200 / Screen: 1067 Lux (bei 200 cm Screen)
Contrast	Projector: 2600:1 full on/off / Screen: 2600:1 full on/off
Black Level	Projector: 1,2308 min. Lumen / Screen: 0,411 min. Lumen
Offset	-
Resolution	XGA 1024 x 768 786.432 Pixel SXGA 1280 x 1024 compressed
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
3D Compatibility	Frame Sequential (3D Ready)
Application	Standard-Portabel | External training and company presentations, as well as product presentations. Medium screen width or rooms with a little more ambient light, max. 200 lumens.
Light Source	230W SHP Lamp
Light Life	3000 h.
Operating Costs	-
Focus	Manual
Zoom	Manual 1,1
Objective	-
Throw Ratio	1,94-2,13:1
Audio	-
Connections	D-sub 15 pin in und out S-Video in Cinch Video in RS232C USB Typ B
Ceiling Mounting	Yes
Power	280W
Size WxHxD	264 x 78 x 208 mm (10,4"x3,1"x8,2") 4,28 L/dm³
Operating Noise	36dB
Weight	2,50 kg / 5,51 lbs.
Keystone	Vert.: +/-15°
Illumination	85%
Frequenz	H-sync: 15-110 kHz V-sync: 50-80 Hz
Foot-Lamberts	99 fL / max. 493 cm screen width 339 cd/m²





Features	■ Eco Mode ■ 6-segment colour wheel.
Status	2011 Discontinued (EOL) // Last update of the data: 2023-08-04
Data	
More Details	https://www.projector-database.com/pro/actodx128-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.