

ASK Proxima C250W

ASK PROXIMA C250W



A brief introduction to the ASK Proxima C250W. The standard portable DLP projector has a WXGA 1280 x 800 resolution and a contrast of 1400:1. A built-in horizontal and vertical keystone correction provides freedom when positioning the projector. An image width of up to 508 cm is possible as the projector has 2500 Ansi lumens. However, if room light is available, the image should be max. 339 cm wide. The model was built by ASK Proxima in 2007 and is no longer current.



1 x 0,65" DDR DLP Chip
WXGA 16/10 Ti Digital Light Processing Chip

Projector	2500 / 1800 im Eco Mode	Screen	1000 Lux (bei 200 cm Screen)
	1400:1 full on/off		1400:1 full on/off
	1,7857 min. Lumen		0,716 min. Lumen

Resolution: WXGA 1280 x 800
1.049.088 Pixel

Video Modes: PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Application: Standard-Portabel | External training and company presentations, as well as product presentations.
Medium screen width or rooms with little light, max. 100 lumens.

Light Source: 220 / 160W im Eco Mode Lamp
Articel Nr.: SP-LAMP-026

Light Life: 2000 h. 3500 h. in Eco Mode

-

Manual


Manual 1,2

F=2,3-2,7 f=23,6-28,25 mm

1,85-2,29:1

1 x 3W Mono

DVI M1DA
D-Sup 15 pin in und out
S-Video in
Cinch Video in
Mini jack Audio in und out
RS232C



Brief Introduction

Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Offset

Resolution

Video Modes

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Connections


Ceiling Mounting Yes
Power 272 / 205W in Eco Mode
Size WxHxD 263,1 x 74,4 x 132,3 mm (10,4"x2,9"x5,2") 2,57 L/dm³
Operating Noise 35 / 32 dB in Eco Mode

Weight 2,27 kg / 5 lbs.
Keystone Vert.: +/-30°
Hori.: +/-30°
Illumination 95%
Frequenz H-sync: 15,6-85 kHz
V-sync: 48-85 Hz
Foot-Lamberts 93 fL / max. 508 cm screen width
319 cd/m²

- Features
- Blank (Black screen button)
 - Eco Mode
 - BrilliantColor™
 - Overscan adjustable
 - 6-segment colour wheel.

Lamp ruby Ruby-LMP16364
Lamp original SP-LAMP-026
Optional Compatible lamp LMP-K16364
Universal Remote original Fernb-uni-V3
Ceiling Mount 100-120 Halterung100

Status Order here: <https://www.hcinema.de/lampen/shop-en.php?id=d18098>
2007 Discontinued (EOL) // Last update of the data: 2023-08-04



HCinema

<https://www.projector-database.com/pro/askproximac250w-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.