
Barco OverView DR120



Brief Introduction Beta 2.5	The Barco OverView DR120 DLP projector has 800 Ansi lumens, a contrast of 1000:1 and an SXGA 1280 x 1024 resolution. An image width of up to 239 cm is possible. However, the image should be smaller in room light. We recommend max. 159 cm. The model was built by Barco in 2006 and is no longer current.
Display Type	DLP Chip SXGA 5/4 Ti Digital Light Processing Chip
Ansi-Lumen	Projector: 800 / Screen: 250 Lux (bei 200 cm Screen)
Contrast	Projector: 1000:1 full on/off / Screen: 1000:1 full on/off
Black Level	Projector: 0,8000 min. Lumen / Screen: 0,251 min. Lumen
Offset	-
Resolution	SXGA 1280 x 1024 1.310.720 Pixel UXGA 1600 x 1200 compressed
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
Application	Stationary | Permanent installation in the training room and meeting room as well as the conference room. Small screen width, rooms with very little ambient light below 100 lumens.
Light Source	120W UHP Lamp
Light Life	-
Operating Costs	-
Focus	Powered
Zoom	Powered 1,17
Objective	-
Throw Ratio	1,2-1,4:1
Audio	No
Connections	D-sub 15pin in 5 x BNC RGBHV in RS232C in und out
Ceiling Mounting	-
Power	230W
Size WxHxD	535 x 296 x 354 mm (21,1"x11,7"x13,9") 56,06 L/dm³
Operating Noise	-





BARCO OVERVIEW DR120

Weight	20,00 kg / 44,09 lbs.
Keystone	-
Illumination	-
Frequenz	H-sync: 15-115 kHz V-sync: 15-150 Hz Range max.: 205 MHz
Foot-Lamberts	23 fL / max. 239 cm screen width 79 cd/m²
Features	-

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Fix Optional Lenses					
Barco Objektiv 2	0.7:1	1.4 m			No Zoom
Barco Objektiv 1	0.92:1	1.8 m			No Zoom

Status 2006 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details

https://www.projector-database.com/pro/barcooverviewdr120-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.