

Boxlight SP 11i



Brief Introduction Beta 2.5	The standard portable Boxlight SP 11i LCD projector has 1200 Ansi lumens, a contrast of 300:1 and an SVGA 800 x 600 resolution. A picture width of up to 302 cm is possible. However, the image should be smaller in room lighting. We recommend max. 201 cm. The model was built by Boxlight in 2003 and is no longer current. It should also be noted that there are unfortunately no more replacement lamps available for the projector, neither originals nor replicas.
Display Type	3 x 0,55" LCD TFT Panel mit MLA SVGA 4/3 Liquid Crystal Display with Micro Lense Array
Ansi-Lumen	Projector: 1200 / 960 im Eco Mode — Screen: 388 Lux (bei 203 cm Screen)
Contrast	Projector: 300:1 full on/off — Screen: 300:1 full on/off
Black Level	Projector: 4,0000 min. Lumen — Screen: 1.307 min. Lumen
Offset	
Resolution	SVGA 800 x 600 480.000 Pixel XGA 1024 x 768 compressed
Video Modes	NTSC, PAL (-BGDHI), SECAM, PAL-M, -N, NTSC4.43, PAL60 SDTV 525i(480i), 525p(480p), 625i(575i)
Application	Standard-Portabel | External training and company presentations, as well as product presentations. Small screen width, rooms with very little ambient light below 100 lumens.
Light Source	130W UHB Lamp Articel Nr.: SP-11t
Light Life	2000 h. 4000 h. in Eco Mode
Operating Costs	-
Focus	Manual
Zoom	Manual 1,2
Objective	F=1,6-1,8 f=16,8-20,2 mm
Throw Ratio	1,5-1,81:1
Audio	1,0W Mono
Connections	1 x RGB analogue - 15-pin HD D-sub 1 x Audio - stereo mini-jack RCA Jack x2 for Video Input Stereo Mini Jack x1 for Data Input RCA Jack x1 S-Video Jack x1 RCA Jack x3 for Component



BOXLIGHT SP 11i

	9-pin D-sub x 1 for RS232 Control 
Ceiling Mounting	Yes
Power	220W
Size WxHxD	332 x 92 x 254 mm (13,1"x3,6"x10") 7,76 L/dm³
Operating Noise	32 / 27 dB in Eco Mode
Weight	2,90 kg / 6,39 lbs.
Keystone	-
Illumination	-
Frequenz	H-sync: 15-91 kHz V-sync: 50-120 Hz
Foot-Lamberts	36 fL / max. 302 cm screen width 123 cd/m²
Features	■ Freeze ■ Blank (Black screen button) ■ Eco Mode ■ Gamma correction ■ Overscan adjustable
Status	2003 Discontinued (EOL) // Last update of the data: 2023-08-04
Data	
More Details	HCinema https://www.projector-database.com/pro/boxlightsp11i-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.