

Christie DHD700

CHRISTIE DHD700



Brief Introduction

Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Lens shift

Resolution

Video Modes

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Connections

Ceiling Mounting

With the DHD700, manufacturer Christie offers a stationary DLP projector with HDTV 1920 x 1080 resolution and a contrast of 7500:1. The built-in lens shift and keystone correction function provides freedom when setting up. 819 cm image width, the projector will be able to illuminate well. The projector can create rooms with residual light with a smaller image width, we would recommend a maximum of 546 cm here. If the image is still too small, the integrated edge blending software can help to project a larger image with additional projectors. The model is also Full HD 1080P compatible. Even projection onto the ceiling is possible thanks to the 360° 1/2 projection. The model was built by Christie in 2009 and is no longer current.



1 x 0,95" DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Projector
6500
7500:1
0,8667 min. Lumen

Vert.: +/-41,5% Hori.: +/-37%

HDTV 1920 x 1080

2.073.600 Pixel

PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

2 x 330W UHP Lamp

Articel Nr.: 003-120504-01

2000 h. 2500 h. in Eco Mode

Powered

Powered

optional

optional

DVI-D in

HDMI 1.3b in

5 x BNC RGBHV in


RJ45 in

RS232C Din 9pin in

USB Typ B

Yes

Screen
2889 Lux (bei 200 cm Screen)
7500:1
0,385 min. Lumen




Screen: 1 Gain

Power 823W
Size WxHxD 400 x 242,5 x 523,5 mm (15,7"x9,5"x20,6") 50,63 L/dm³
Operating Noise 39 / 36 dB in Eco Mode

Weight 19,70 kg / 43,43 lbs.
Keystone Vert.: +/-30°
Hori.: +/-30°
Illumination 90%
Frequenz H-sync: 15-120 kHz
V-sync: 48-120 Hz
Range max.: 160 MHz
Foot-Lamberts 268 fL / max. 819 cm screen width
918 cd/m²

Features

- Full HD 1080P compatible
- Lens shift Funktion
- Eco Mode
- Warping
- 360° installable
- 24/7 continuous operation capable
- Edge Blending
- Picture-in-Picture
- Remote control with backlight
- Optional Wi-Fi network compatible.
- Lan network compatible.



Philips bulb only NLMP19106
Lamp ruby Ruby-LMP19106
Lamp original 003-120504-01
Compatible lamp LMP-K19019

Optional Remote control original 6451024619 / CXZZ

Air filter compatible Alternative zu:ET-SFYL131 / POA-FIL-131 / 610-334-3747 / 003-001726-01

Air filter original ET-SFYL131 / POA-FIL-131 / 610-334-3747 / 003-001726-01

Ceiling Mount 220 Halterung45

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n19019>

Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
Ultra Long Zoom HD 4.8-8.0:1	4.8-8:1	9.6-16 m	+/-41.5%	+/-37%	Powered
Standard Zoom HD 1.8-2.8:1	1.8-2.8:1	3.6-5.6 m	+/-41.5%	+/-37%	Powered
Short Zoom HD 1.2-1.5:1	1.2-1.5:1	2.4-3 m	+/-41.5%	+/-37%	Powered
Long Zoom HD 2.8-5.0:1	2.8-5:1	5.6-10 m	+/-41.5%	+/-37%	Powered
Fix Optional Lenses					
Fix Lens HD 0.8:1	0.8:1	1.6 m	0.0% Fix		No Zoom
Status	2009 Discontinued (EOL) // Last update of the data: 2023-08-04				



More Details



HCinema

<https://www.projector-database.com/pro/christiedhd700-en.html>