
EZCast Beam J2



Brief Introduction Beta 2.5	The Beam J2 LED DLP has 300 Ansi-Lumen, a contrast of 5000:1 and a WVGA 854 x 480 resolution. It is an LED projector with 20000 hours of light life, which is the equivalent of over 13.7 years at 4 hours per day. The projector can illuminate a picture width of up to 176 cm well thanks to the 300 Ansi lumens. In room light, however, the image width should ideally be less than 117 cm. Thanks to the built-in 9000 mAh battery, no power supply is required, allowing the projector to be set up quickly and flexibly. As the projector recognizes DLNA, Airplay, Miracast Screen Mirroring signals, it is possible to play videos with a high resolution and surround sound directly from a smartphone, tablet, PC (Android, Windows and iOS) via WLAN. It is also Full HD 1080P compatible. The model was built by EZCast 2020 and is no longer current.
Display Type	DLP Chip WVGA 16/9 Ti Digital Light Processing Chip
Ansi-Lumen	Projector: 300 / Screen: 133 Lux (bei 200 cm Screen)
Contrast	Projector: 5000:1 / Screen: 5000:1
Black Level	Projector: 0,0600 min. Lumen / Screen: 0,027 min. Lumen
Offset	-
Resolution	WVGA 854 x 480 409.920 Pixel
Video Modes	Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, EDTV 480p, 576p
Application	Game-Portabel | Very portable, small-screen projections. Very narrow picture width and rooms with very little light.
Light Source	LED
Light Life	20000 h.
Operating Costs	0,00 € LED
Focus	Manual
Zoom	No Zoom
Objective	-
Throw Ratio	1,3:1
Audio	2W
Connections	USB HDMI 3,5 mm Audio Jack out
Ceiling Mounting	-
Power	-
Size WxHxD	115 x 32 x 115 mm (4,5"x1,3"x4,5") 0,42 L/dm³
Operating Noise	-



EZCAST BEAM J2

Weight	0,400 kg / 0 lbs.
Keystone	-
Illumination	-
Frequenz	-
Foot-Lamberts	12 fL / max. 176 cm screen width 41 cd/m²
Features	■ Full HD 1080P compatible ■ Automatic and manual vertical keystone correction ■ Wi-Fi network compatible. ■ 9000 mAh

Optionaler Zubehör

Status	2020 Discontinued (EOL) // Last update of the data: 2024-11-08
Data	Created: 2020-05-26 17:16:16
More Details	https://www.projector-database.com/pro/exstreamvisionbeamj2-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.