
Optoma EzPro / EP729



Brief Introduction Beta 2.5	The micro-portable EzPro / EP729 DLP has 1600 Ansi lumens, a contrast of 2200:1 and an XGA 1024 x 768 resolution. The lamp has a service life of up to 4000 hours, which is over 5.5 years if enjoyed for two hours a day. 1600 Ansi lumens ensure that a picture width of 348 cm is also possible. However, if room light is available, the picture should be max. 232 cm wide. The model was built by Optoma in 2005 and is no longer current, but is still very popular in our projector database.
Display Type	1 x 0,7" DDR DLP Chip XGA 4/3 Ti Digital Light Processing Chip


	Projector	Screen
Ansi-Lumen	1600	533 Lux (200 cm Screen width)
Contrast	2200:1 full on/off	2200:1 full on/off
Black Level	0,7273 min. Lumen	0,243 min. Lumen
Offset		

Resolution	XGA 1024 x 768 786.432 Pixel SXGA 1280 x 1024 compressed
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
Application	Micro-Portabel | Small mobile presentations.. Small screen width, rooms with very little ambient light below 100 lumens.
Light Source	156W P-VIP Lamp Article Nr.: SP.82F01.001
Light Life	4000 h. 3000 h. in Bright Mode
Operating Costs	-
Focus	Manual
Zoom	Manual 1,15
Objective	F=2,7-2,88 f=28,43-32,75 mm
Throw Ratio	2,0-2,3:1
Audio	Nein
Connections	D-sub 15pin in Cinch Video in S-Video in USB





Ceiling Mounting	No, is not possible.
Power	195W / 10W standby
Size WxHxD	152 x 62,4 x 200 mm (6"x2,5"x7,9") 1,88 L/dm³
Operating Noise	33dB



Weight	1,00 kg / 2,2 lbs.
Keystone	Vert.: +/-16°
Illumination	85%
Frequenz	H-sync: 31,5-80 kHz V-sync: 56-85 Hz
Foot-Lamberts	50 fL / max. 348 cm screen width 171 cd/m²
Features	■ Freeze ■ User logo ■ Kensington Slot ■ sRGB ■ Remote control with laser pointer und mouse control ■ De-interlacer with 3:2 and 2:2 pull down
Screen Mirroring	-

Optional accessories

	Nackte Osram Lampe	NLMP2624	127,63 €
	Lampe Ruby	Ruby-LMP2624	87,64 €
	Lampe Original	BL-FP156A / SP.82F01.001	EOL €
	Kompatible Lampe	LMP-K2624	55,24 €
	Universal Fernbedienung	Fernb-uni-V3	22,31 €
	Fernbedienung Original	45.82F01.001	EOL €

Status 2005 Discontinued (EOL) // Last update of the data: 2026-06-09

Data



More Details

HCinema

https://www.projector-database.com/pro/optomaep729-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.