

Optoma HT50

OPTOMA HT50



With the HT50, manufacturer Optoma offers a standard portable DLP projector with HDTV 1920 x 1080 resolution and a contrast of 50000:1. An image width of up to 477 cm is possible. However, the image should be smaller in room light. We recommend max. 318 cm. Playing 1080P and 3D is also no problem for the projector. The model was built by Optoma in 2015 and is no longer current.



1 x DC3 DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Projector	2200	978 Lux (bei 200 cm Screen)
Contrast	50000:1 full on/off	50000:1 full on/off
Black Level Offset	0,0440 min. Lumen	0,02 min. Lumen

Resolution
HDTV 1920 x 1080
2.073.600 Pixel

Video Modes
Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p
3D Compatibility
Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom
Frame Sequential (3D Ready)

Application
Standard-Portabel | External training and company presentations, as well as product presentations.

Light Source
Medium screen width or rooms with little light, max. 100 lumens.

Light Life
3000 h. 7000 h. in Eco Mode

Operating Costs
-

Focus
Manual


Zoom
Manual 3,66

Objective
F=2,42-2,97 f=20,7-31,05 mm


Throw Ratio
1,39-5,09:1

Audio
-

Connections
2 x HDMI 1.4a in
D-sub 15pin in
YUV in
Cinch Video in
Cinch Stereo in
S-Video in
Mini Jack Audio in und out
USB in
RS232C Din 9 pin in
12V Trigger out



Brief Introduction
Beta 2.5



Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
-
289 x 129 x 269 mm (11,4"x5,1"x10,6") 10,03 L/dm³
32dB

Weight
Keystone
Illumination

3,50 kg / 7,72 lbs.
Vert.: +/-40°
85%

Frequenz

-

Foot-Lamberts

91 fL / max. 477 cm screen width
312 cd/m²



Features

- Real Full HD 3D
- Full HD 1080P compatible
- Eco Mode
- Kensington Slot

Status

2015 Discontinued (EOL) // Last update of the data: 2023-08-04
Created: 2015-09-08 13:41:02

Data



More Details



HCinema

<https://www.projector-database.com/pro/optomaht50-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.