

Optoma TW631 3D

OPTOMA TW631 3D



A brief introduction to the TW631 3D: The Optoma 3D BrilliantColor DLP projector offers 3500 Ansi lumens, a contrast of 8000:1 and a WXGA 1280 x 800 resolution. Thanks to the lamp, the projector has a lamp life of up to 3500 hours, which is over 4.8 years if enjoyed for two hours a day. An image width of up to 601 cm is possible as the projector has 3500 Ansi lumens. The projector creates rooms with residual light with a smaller image width, we recommend a maximum of 401 cm. Even 1080P video signals are no problem for the projector. The model was built by Optoma in 2012 and is no longer current.

 1 x 0,65" DC3 DLP Chip
WXGA 16/10 Ti Digital Light Processing Chip

Projector	3500	Screen	1400 Lux (bei 200 cm Screen)
	8000:1 full on/off		8000:1 full on/off
	0,4375 min. Lumen		0,175 min. Lumen

Resolution
WXGA 1280 x 800
1.024.000 Pixel

Video Modes
Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

3D Compatibility
Frame Sequential (3D Ready) 120Hz Frame sequential 3D for resolutions up to 720p,
60Hz field sequential 3D for resolutions up to 480i

Application
Standard-Portabel | External training and company presentations, as well as product presentations.

Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Source
240W P-VIP Lamp

Articel Nr.: BL-FP240A

Light Life
3500 h. 6000 h. in Eco Mode

Operating Costs
-

Focus
Manual

Zoom
Manual 1,23


Objective
F=2,57-2,84 f=21,0-25,6 mm

Throw Ratio
1,47-1,81:1

Audio
7W

Connections
HDMI 1.3 in
2 x D-sub 15 pin in 1 x out
S-Video in
Cinch Video in
Mini Jack Audio in und out
RJ45 in

Ceiling Mounting
Yes



Power 300 / 230W in Eco Mode
Size WxHxD 280 x 78,4 x 230 mm (11"x3,1"x9,1") 5,02 L/dm³
Operating Noise 31 / 29 dB in Eco Mode

Weight 2,20 kg / 4,85 lbs.
Keystone Vert.: +/-40°
Illumination 91,1%

Frequenz H-sync: 24-120 kHz
V-sync: 15,3 Hz

Foot-Lamberts 130 fL / max. 601 cm screen width
445 cd/m²

- Full HD 1080P compatible
- Eco Mode
- Kensington Slot
- BrilliantColor™
- Remote control with laser pointer und mouse control
- Lan network compatible.
- Crestron®-Software compatible.

Optional Remote control original BR-5035N
Lamp original BL-FP240A

Status Order here: <https://www.hcinema.de/lampen/shop-en.php?id=fro21215>
2012 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details



HCinema

<https://www.projector-database.com/pro/optomatw6313d-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.

