
Optoma W505



DLP | 3D ready | DICOM Simulation | Lens Shift | Motor | PJLink | Netzwerk | CRESTRON Steuerung | USB


Brief Introduction Beta 2.5	A brief introduction to the Optoma W505. The DLP projector has a WXGA 1280 x 800 resolution and a contrast of 2000:1. The built-in lens shift function provides freedom when setting up. The projector can illuminate a screen width of 733 cm well. The projector can create rooms with residual light with a smaller image width, max. 489 cm is recommended here. The model was built by Optoma in 2013 and is no longer current.
Display Type	1 x 0,65" DLP Chip WXGA 16/10 Ti Digital Light Processing Chip
Ansi-Lumen	Projector: 5200 / Screen: 2080 Lux (bei 200 cm Screen)
Contrast	Projector: 2000:1 full on/off / Screen: 2000:1 full on/off
Black Level	Projector: 2,6000 min. Lumen / Screen: 1,041 min. Lumen
Lens shift	Vert.: +70% -20% Hori.: +/-10%
Resolution	WXGA 1280 x 800 1.024.000 Pixel
Video Modes	Pal, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
3D Compatibility	Frame Sequential (3D Ready)
Application	Stationary | Permanent installation in the training room and meeting room as well as the conference room. Wide screen width or rooms with plenty of light (over 200 lumens).
Light Source	370W UHP Lamp Articel Nr.: 5811118128-SOT / BL-FP370A
Light Life	1500 h. 3500 h. in eco Mode
Operating Costs	7,62% / 0,25 €
Focus	Powered
Zoom	Powered
Objective	optional
Throw Ratio	optional
Audio	2 x 3W
Connections	HDMI in DVI-D in 2 x D-sub 15pin in 1 x out 5 x BNC RGBHV in Cinch Video in Cinch Stereo in S-Video in Mini Jack Audio in und out USB in RS232C Din 9 pin in RJ45 in 12V Trigge rout



OPTOMA W505



Ceiling Mounting	Yes
Power	460W
Size WxHxD	431 x 183 x 341 mm (17"x7,2"x13,4") 26,9 L/dm³
Operating Noise	37 dB in Eco Mode



Weight	8,60 kg / 18,96 lbs.
Keystone	-
Illumination	85%
Frequenz	-
Foot-Lamberts	193 fL / max. 733 cm screen width 661 cd/m²

Features

- Lens shift Funktion
- Eco Mode
- PJLink™
- Lan network compatible.
- Crestron®-Software compatible.

Optional

Remote control original	BR-3070L, SP.72101GC01
Lamp original	5811118128-SOT / BL-FP370A

Order here: https://www.hcinema.de/lampen/shop-en.php?id=fro22059

Status

2013 Discontinued (EOL) // Last update of the data: 2023-08-04
Created: 2013-06-25 10:19:58

Data




More Details

HCinema
https://www.projector-database.com/pro/optomaw505-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.