
Optoma X416



OPTOMA X416

Brief Introduction Beta 2.5	With the X416, manufacturer Optoma offers a DLP projector with XGA 1024 x 768 resolution and a contrast of 20000:1. Includes a lens shift and keystone correction function, which provides freedom during installation. A picture width of up to 571 cm is possible, if the picture width is smaller (we recommend max. 381 cm), rooms with residual light are also no problem. A smartphone with MHL connection can be connected directly to the MHL/HDMI port for 1080p / 60 Hz image mirroring (screen mirroring). Video signals 1080P and 3D are also no problem for the projector. The model was built by Optoma in 2016 and is no longer current.
Display Type	1 x 0,65" DC3 DLP Chip XGA 4/3 Ti Digital Light Processing Chip
Ansi-Lumen	Projector: 4300 / Screen: 1433 Lux (bei 200 cm Screen)
Contrast	Projector: 20000:1 full on/off / Screen: 20000:1 full on/off
Black Level	Projector: 0,2150 min. Lumen / Screen: 0,072 min. Lumen
Lens shift	Vert.: +65% --48,1%
Resolution	XGA 1024 x 768 786.432 Pixel UXGA 1600 x 1200 compressed
Video Modes	Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p
3D Compatibility	Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom Frame Sequential (3D Ready)
Application	Standard-Portabel | External training and company presentations, as well as product presentations. Wide screen width or rooms with plenty of light (over 200 lumens).
Light Source	260W Lamp Articel Nr.: SP.72Y01GC01 / BL-FU260C
Light Life	3000 h. 7000 h. in Eco Mode
Operating Costs	19,05% / 0,08 €
Focus	Manual
Zoom	Manual 1,37
Objective	F=2,51-2,93 f=15,98-21,42 mm
Throw Ratio	1,39-1,9:1
Audio	1 x 10W
Connections	2 x HDMI 1.4a mit MHL in D-sub 15pin in und out Cinch Video in Mini Jack Audio in und out USB Typ A in RS232C Din 9 pin in



RJ45 in



Ceiling Mounting	Yes
Power	309 / 249W in Eco Mode
Size WxHxD	314 x 114 x 224 mm (12,4"x4,5"x8,8") 8,02 L/dm³
Operating Noise	32 dB in Eco Mode



Weight	2,99 kg / 6,59 lbs.
Keystone	Vert.: +/-40°
Illumination	80%
Frequenz	H-sync: 15-91 kHz V-sync: 24-120 Hz
Foot-Lamberts	133 fL / max. 571 cm screen width 456 cd/m²

Features

- Real Full HD 3D
- Full HD 1080P compatible
- Lens shift Funktion
- Eco Mode
- Kensington Slot
- Password protection
- BrilliantColor™
- Lan network compatible.

Optional

Lamp original	SP.72Y01GC01 / BL-FU260C
Remote control original	BR-5053C/BR-5080C/SP.72702GC01

Status

Order here: https://www.hcinema.de/lampen/shop-en.php?id=23833
2016 Discontinued (EOL) // Last update of the data: 2023-09-20
Created: 2016-04-06 10:02:29

Data



More Details

HCinema
https://www.projector-database.com/pro/optomax416-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.