

Optoma X502



OPTOMA X502



The X502 3D DLP has 5000 Ansi lumens, a contrast of 10000:1 and an XGA 1024 x 768 resolution. The integrated lens shift gives freedom when positioning the projector. As the X502 is equipped with a microphone jack and 16W loudspeakers, no additional audio system is required for presentations or training courses. The projector can illuminate images up to 616 cm wide thanks to its 5000 Ansi lumens. The projector can create rooms with residual light with a smaller image width, max. 411 cm is recommended. The HDMI MHL (Mobile High-Definition Link) port allows 1080p / 60 Hz image mirroring (screen mirroring) to be transmitted from the smartphone while it is being charged at the same time via the connection. The projector can also play 1080P and 3D without any problems. With only 30 decibels of operating noise, the model is already very quiet compared to others. The model was built by Optoma in 2015 and is no longer current.

Brief Introduction

Beta 2.5

Display Type



1 x 0,65" DLP Chip
XGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

Projector 5000

Screen 1667 Lux (bei 200 cm Screen)

Contrast

Projector 10000:1 full on/off

Screen 10000:1 full on/off

Black Level

Projector 0,5000 min. Lumen

Screen 0,167 min. Lumen

Lens shift

Vert.: +65% -48,1%

Resolution

XGA 1024 x 768
786.432 Pixel

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p

3D Compatibility

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom
Frame Sequential (3D Ready)

Application

Standard-Portabel | External training and company presentations, as well as product presentations.
Wide screen width or rooms with plenty of light (over 200 lumens).

Light Source

-

Light Life

Articel Nr.: SP.70B01GC01 / BL-FU310D
3500 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,59

Objective

-

Throw Ratio


1,85-2,94:1

Audio

2 x 16W

Connections

2 x HDMI 1.4a mit MHL in
D-sub 15pin in und out
Cinch Video in
S-Video in
Mini Jack Audio in und out
USB in
RS232C Din 9 pin in
RJ45 in
12V Trigger out
Mikrofon in





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
-
369 x 132 x 295 mm (14,5"x5,2"x11,6") 14,37 L/dm³
30dB

Weight
Keystone
Illumination

4,60 kg / 10,14 lbs.
Vert.: +/-30°
Hori.: +/-30°
85%

Frequenz

-

Foot-Lamberts

155 fL / max. 616 cm screen width
531 cd/m²


- Real Full HD 3D
- Full HD 1080P compatible
- Lens shift Funktion
- Eco Mode
- Kensington Slot
- PJLink™
- Lan network compatible.
- Crestron®-Software compatible.

Features

Status

2015 Discontinued (EOL) // Last update of the data: 2023-09-20
Created: 2015-12-03 16:01:41

Data



More Details



HCinema

<https://www.projector-database.com/pro/optomax502-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.