
Sharp XV Z12000E/U



Brief Introduction Beta 2.5	A brief introduction to the XV Z12000E/U: The Sharp DLP projector offers 900 Ansi lumens, a contrast of 3000:1 / 5500:1 (HIGH brightness mode) and HDTV 1280 x 720 resolution. With the lens shift function, the projector can be positioned very freely. An image width of up to 305 cm is possible as the projector has 900 Ansi lumens. However, if room light is available, the picture should be a maximum of 203 cm wide. The model was built by Sharp in 2003 and is no longer current.
Display Type	1 x 0,8" DLP HD2+ Mustang Chip HDTV 16/9 Ti Digital Light Processing Chip
Ansi-Lumen	Projector: 900 (Helligkeitsmodus HIGH) / Screen: 388 Lux (bei 203 cm Screen)
Contrast	Projector: 3000:1 / 5500:1 (Helligkeitsmodus HIGH) / Screen: 3000:1 / 5500:1 (Helligkeitsmodus HIGH)
Black Level	Projector: 0,3000 min. Lumen / Screen: 0.129 min. Lumen
Lens shift	Vert.: +/-50% manuell
Resolution	HDTV 1280 x 720 921.600 Pixel HDTV 1920 x 1080 compressed
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
Disc Recognition	DVD | HD Blu-ray (komprimiert) | ~~3D Blu-ray~~ | ~~4K UHD Blu-ray~~
Application	Homeciname | Small screen width, rooms with very little ambient light below 100 lumens.
Light Source	270W SHP Lamp Articel Nr.: BQC-XVZ100005
Light Life	2000 h.
Operating Costs	-
Focus	Manual
Zoom	Manual 1,35
Objective	F=2,5 f=32,5-44,0 mm
Throw Ratio	1,8-2,5:1
Audio	No
Connections	DVI-I mit HDCP in D-sub 15pin in 2 xRGBHV per 5 x Cinch Eingang S Video Eingang Cinch Video in Mini Jack Eingang RS232C
Ceiling Mounting	Yes



SHARP XV Z12000E/U

Power	365W
Size WxHxD	475 x 178 x 406 mm (18,7"x7"x16") 34,33 L/dm³
Operating Noise	33dB



Weight	9,40 kg / 20,72 lbs.
Keystone	-
Illumination	95%
Frequenz	H-sync: 15,0-81,0 kHz V-sync: 43-100 Hz Range max.: 120 MHz
Foot-Lamberts	36 fL / max. 305 cm screen width 123 cd/m²
Features	■ Lens shift Funktion manuell ■ Kensington Slot ■ Gamma correction ■ Dynamic iris ■ Remote control with backlight ■ High-Contrast Optical Engine completely eliminates unwanted light ■ High-performance image processing LSI that integrates all digital image processing functions on a single chip ■ Civic-2 deinterlacer with film mode detection ■ 7-segment colour wheel with 5x speed
In Test	-
Please note	Irisblende kann per Fernbedienung verstellt werden.

Optional

Bulb only	NLMP3779
Lamp ruby	Ruby-LMP3779
Lamp original	BQC-XVZ100005 / AN-K12LP
Compatible lamp	LMP-K15702
Universal Remote original	Fernb-uni-V3

Order here: https://www.hcinema.de/lampen/shop-en.php?id=n3779

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
Sharp AN-W9Z (Vorsatzobjektiv)	1.5-2:1	3-4.1 m	+/-50%		Manual

Status 2003 Discontinued (EOL) // Last update of the data: 2023-08-04

Data






More Details

https://www.projector-database.com/pro/sharpxvz12000-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.