

Videoseven PD480C



Brief Introduction Beta 2.5	The Videoseven PD480C home cinema DLP projector has 1100 Ansi lumens, a contrast of 2000:1 and a WVGA 854 x 480 resolution. The projector can illuminate a picture width of up to 337 cm thanks to the 1100 Ansi lumens. In room light, however, the image width should ideally be less than 225 cm. The model was built by Videoseven in 2005 and is no longer current.
Display Type	1 x 0,55" DDR DLP Chip WVGA 16/9 Ti Digital Light Processing Chip
Projector: Ansi-Lumen	1100
Projector: Contrast	2000:1 full on/off
Projector: Black Level Offset	0,5500 min. Lumen
Screen	489 Lux (bei 200 cm Screen) 2000:1 full on/off 0,245 min. Lumen
Resolution	WVGA 854 x 480 409.920 Pixel SXGA 1280 x 1024 compressed
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
Disc Recognition	DVD | HD Blu-ray (komprimiert) | ~~3D Blu-ray~~ | ~~4K UHD Blu-ray~~
Application	Homeciname | Small screen width, rooms with very little ambient light below 100 lumens.
Light Source	200W Osram Lamp Articel Nr.: LMP15689
Light Life	2000 h.
Operating Costs	8,22% / 0,06 €
Focus	Manual
Zoom	Manual 1,2
Objective	f=22-26,7 mm
Throw Ratio	1,83-2,19:1
Audio	1 x 2W
Connections	D-sub 15pin in Cinch Video in S-Video in Mini Jack in USB
Ceiling Mounting	Yes





VIDEOSEVEN PD480C

Power	260W
Size WxHxD	254 x 98 x 202 mm (10"x3,9"x8") 5,03 L/dm³
Operating Noise	34 / 32 dB in Eco Mode



Weight	2,20 kg / 4,85 lbs.
Keystone	Vert.: +/-15°
Illumination	80%
Frequenz	H-sync: 31-79 kHz V-sync: 50-85 Hz Range max.: 135 MHz
Foot-Lamberts	45 fL / max. 337 cm screen width 154 cd/m²
Features	■ Blank (Black screen button) ■ Eco Mode ■ Gamma correction ■ De-interlacer with 3:2 pull down

Optional		
	Bulb only Osram	NLMP15689
	Lamp ruby	Ruby-LMP15689
	Lamp original	LMP15689

Order here: https://www.hcinema.de/lampen/shop-en.php?id=n15689

Status 2005 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details

https://www.projector-database.com/pro/videosevenpd480c-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.