
Visbox VisMini



3LCD USB

Brief Introduction Beta 2.5	The Visbox VisMini micro-portable LCD projector has 3000 Ansi lumens, a contrast of 2000:1 and a WXGA 1280 x 800 resolution. 556 cm image width, the projector will be able to illuminate well. However, if room light is available, the image width should ideally not exceed 371 cm. The model was built by Visbox in 2009 and is no longer current, but is still one of the very popular projectors.
Display Type	3 x 0,74" LCD TFT Panel WXGA 16/10 Liquid Crystal Display
Projector Ansi-Lumen	3000 / 6000 beide Projektoren
Projector Contrast	2000:1 full on/off
Projector Black Level Offset	1,5000 min. Lumen
Screen	1200 Lux (bei 200 cm Screen)
Screen	2000:1 full on/off
Screen	0,601 min. Lumen
Resolution	WXGA 1280 x 800 1.024.000 Pixel UXGA 1600 x 1200 compressed
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p
Application	Micro-Portabel | Mobile presentations and external training. Medium screen width or rooms with a little more ambient light, max. 200 lumens.
Light Source	170W UHE Lamp
Light Life	3000 h.
Operating Costs	-
Focus	Manual
Zoom	Manual 1,19
Objective	F=1,6-1,74 f=16-19 mm
Throw Ratio	1-1,19:1
Audio	-
Connections	D-sub 15 pin in S-Video in Cinch Video in USB Typ B
Ceiling Mounting	-
Power	243W
Size WxHxD	284 x 65 x 202 mm (11,2"x2,6"x8") 3,73 L/dm³
Operating Noise	-
Weight	1,17 kg / 2,58 lbs.
Keystone	-
Illumination	-
Frequenz	H-sync: 15-92 kHz V-sync: 50-85 Hz
Foot-Lamberts	111 fL / max. 556 cm screen width 380 cd/m²
Features	-
Status	2009 Discontinued (EOL) // Last update of the data: 2023-08-04



VISBOX VISMINI

Data

More Details



HCinema

https://www.projector-database.com/pro/visboxvismini-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.